| OS SUCAR | CITY COUNCIL | | | | | | | | |
|--|---|----------------------------|--|--|--|--|--|--|--|
| TEXAS | AGENDA REQUEST | | | | | | | | |
| AGENDA OF: | 11-19-13 | AGENDA REQUEST NO: | Ш-F | | | | | | |
| INITIATED BY: | TIMOTHY JAHN P.E. SENIOR ENGINEER | RESPONSIBLE DEPARTMENT: | Engineering | | | | | | |
| PRESENTED BY: | TIMOTHY JAHN P.E. TWJ SENIOR ENGINEER | DIRECTOR: | CHRISTOPHER STEUBING, P.E., CFM, CITY ENGINEER CL S | | | | | | |
| | | Additional Director (s): | KENNETH RENEAU, \(\sumsymbol{\subset}\) INTERIM DIRECTOR OF WATER UTILITIES | | | | | | |
| SUBJECT / NORTH WWTP ODOR CONTROL EQUIPMENT – CIP WW1302 PROCEEDING: AUTHORIZE DESIGN SERVICES CONTRACT WITH CAROLLO ENGINEERS | | | | | | | | | |
| EXHIBITS: | LOCATION MAP CAROLLO ENGINEERS SIGNED CONTRACT CAROLLO ENGINEERS PROPOSAL | | | | | | | | |
| CLEARANCES APPROVAL | | | | | | | | | |
| LEGAL: | EUGENIA A. CANO, FIRST ASST. CITY ATTORNEY | EXECUTIVE DIRECTOR: | N/A | | | | | | |
| Purchasing: | TODD REED, CPPB PURCHASING MANAGER | ASSISTANT CITY MANAGER: | KAREN DALY | | | | | | |
| BUDGET: | BRYAN GUINN, ASSISTANT BUDGET & RESEARCH DIRECTOR | CITY MANAGER: | ALLEN BOGARD Colon Boyan | | | | | | |
| | BUDGET | | | | | | | | |
| | Expenditure Required: \$ | 79,349 | | | | | | | |
| | CURRENT BUDGET: \$ | 372,000 | | | | | | | |
| | ADDITIONAL FUNDING: \$ | 0.00 | | | | | | | |
| RECOMMENDED ACTION | | | | | | | | | |

Authorize the execution of a design contract with Carollo Engineers for the North Wastewater Treatment Plant (North WWTP) Odor Control Equipment, CIP WW1302, in the amount of \$79,349.00.

EXECUTIVE SUMMARY

The North Wastewater Treatment Plant (WWTP) is located adjacent to dense residential neighborhoods. With prevailing winds from the south, the City has received several complaints about odor from the surrounding neighbors over the last year or so. The existing odor control system was installed about 15 years ago by Brazos River Authority staff and the system has reached the end of its useful life.

In FY13, Carollo Engineers evaluated the main sources of the odor causing treatment units, characterized the malodorous odor from the units, and included an evaluation of odor control technology with recommendations through a Preliminary Engineering Report (PER).

The results of the PER determined that the main source of offensive odor emissions is from the onsite lift station, head works screen channel, the belt press unit, and the onsite sludge thickener. The main chemical compound contributing to the offensive odor is hydrogen sulfide (H2S), as normally expected for WWTPs.

A phased approached is recommended to address odor control treatment effectiveness at each source. Phase 1 will address the onsite lift station and head works screen channel where the majority of the H2S emissions were measured. Several odor control treatment technologies were evaluated and the recommended treatment option for Phase 1 is a biological treatment system using biotrickling scrubbers. Phase 2, if warranted, will possibly include addressing the belt press unit and the onsite sludge thickener once the effectiveness of Phase 1 is validated.


Biotrickling scrubbers are vendor-supplied units that typically include a fiberglass-reinforced vessel, fans, artificial media sand, gravel, or plastic beads) and control systems. The process typically involves spraying biologically-active, nutrient-rich solutions over the artificial media while the odorous air is forced through the media. The H2S is removed from the air to the media. Biotrickling scrubbers are a cost effective treatment option that have a high efficiency rate of H2S removal, relatively low capital construction costs, relatively low operating costs, and ease of operations.

Phase 1 system improvements are ready to move forward for design. The scope of services for Carollo Engineers will include the following items:

- Project Management / Project Coordination
- Final Design Services
- Surveying
- Preparation of Probable Construction Costs
- Bidding Assistance
- Preparation of Recommendation of Award Letter
- Preparation of Conformed Contract Documents for construction

Carollo Engineers was selected based on interviews held in November 2013 with four firms selected from the City's library of pre-qualified firms and in accordance with the City policy PU-109, Procurement of Professional Services and Consulting. The design amount of \$79,349 was negotiated through a level of effort with Carollo Engineers. Funding for design for this project is available from CIP WW1302 with the design taking three months to complete.

The Engineering and Water Utilities Department recommends that the City Council authorize the execution of a design contract with Carollo Engineers for the North Wastewater Treatment Plant (North WWTP), CIP WW1302 in the amount of \$79,349.00.



CITY OF SUGAR LAND STANDARD CONTRACT FOR PROFESSIONAL ENGINEERING DESIGN SERVICES FOR CITY FACILITIES

Over \$50K - Form Revised 3/1/10

| T. | Genera | lli | form | ation | and | T | erms. |
|----|--------|-----|------|-------|-----|---|-------|
|----|--------|-----|------|-------|-----|---|-------|

| Engineer's Name and Address: | Carollo Engineers, Inc. 9800 Richmond Avenue, Suite 427 Houston, TX 77042 |
|---------------------------------------|---|
| Project Description: | North Wastewater Treatment Plant Odor Control System Design |
| Maximum Contract Amount: | \$79,349.00 |
| Effective Date: On the latest date of | f the dates executed by both parties. |
| Termination Date: (See III F) | |

II. Signatures. By signing below, the City and the Engineer agree to the terms of this Contract.

| CITY OF SUGAR LAND | ENGINEER: |
|--|-------------------------------|
| | By: Ully Thy |
| City Manager or Assistant City Manager | DARRYL CORBIN P.E. |
| Date: | Date: 10/25/2013 |
| APPROVED AS TO FORM: | Pallela |
| Engenia de Cont | PAUL WALKER VICE PRESIDENT |
| | 11/5/12 |

carollo engineerscon 10-16/13

Attachment A City of Sugar Land North Wastewater Treatment Plant Odor System Design Scope of Work

GENERAL

Carollo Engineers, Inc. (ENGINEER) will design the odor control system for the City of Sugar Land (CITY)'s North Wastewater Treatment Plant (NWWTP). A summary report will be prepared that describes the sampling and testing program, presents a summary of findings and provides raw laboratory data as an Appendix. The following scope details the work effort for the Phase 1 Odor Evaluation.

SUBCONSULTANTS

The following subconsultants will perform work on this Project, contracted to Carollo.

Kuo Associates, Inc. - Survey

Task 1 – Project Management. Project controls will be used to guide and manage the activities of the Carollo Team, including the sub-consultant, during execution of the authorized work activities. The following will be performed under this task:

- a. Conduct Project Kick-off Meeting: The kick-off meeting will be held as soon as practical following notice to proceed. The meeting will cover introductions, project roles & responsibilities, expectations, purpose and goals, sampling program protocol and schedule.
- b. Provide ongoing project controls consisting of:
 - Conduct 30%, 60% and 90% review meetings.
 - Plan, organize, staff, direct, manage, coordinate, and report work tasks of project team including subconsultant.
 - Maintain and update project logs (action items, decisions, schedule).
 - Conduct monthly project management meetings with City management staff.
- c. Prepare and submit monthly invoices and status reports including back-up information

Deliverables:

- Kick-off Meeting Agenda, Materials, and Meeting Minutes
- Monthly status reports and invoices
- Project logs and updates

Task 2 – Final Design Services. The Final Engineering Documents prepared by ENGINEER will include all engineering services to carry out the concepts agreed upon by the CITY in the NWWTP Odor Evaluation report. Final Engineering will include designs, construction plans,

specifications, and engineer's estimate for the Project that will enable the CITY to advertise and award the construction contract for the Project.

ENGINEER will prepare plans, specifications, and engineer's construction cost estimates for the Odor Control System such that CITY may advertise and award a construction contract for the Project.

The following describes the Scope of Services for the project to provide reliable odor control system:

- 1. Perform engineering analysis to determine fan size, duct size, and duct routing.
- 2. Develop process and instrumentation diagrams (P&IDs) for the new odor control system.
- 3. Design new 2,200 cfm biofilter odor control system, including concrete pad, and new fan.
- 4. Design new ducts, and required appurtenances necessary to interconnect the odor control system for the lift station, and headworks.
- 5. Disconnect the existing odor control ductwork from the lift station and the headworks.

ENGINEER will prepare contract documents for bidding and construction purposes including construction plans, specifications, and final engineer's construction cost estimate, and copies of data in digital format in the latest version of MS Word for all specifications and in Mircostation for all drawings upon the completion of the Project.

Deliverables:

- 30% Submittal 5 copies of Specifications, 11 x 17 plans, and OPCC
- 60% Submittal 5 copies of Specifications, 11 x 17 plans, and OPCC
- 90% Submittal 5 copies of Specifications, 11 x 17 plans, and OPCC
- 100% Submittal 5 copies of Specifications, 11 x 17 plans, and OPCC

Task 3 – Bidding Assistance. ENGINEER will assist CITY in providing clarification and prepare addenda as needed for questions that may arise during the bidding process. ENGINEER will attend the pre-bid meeting, if any, and record the minutes of the meeting as required and distribute to the CITY.

Deliverables:

- Addenda
- Pre-bid Meeting minutes

SCHEDULE:

The work will be completed within 3 months of notice to proceed.

ASSUMPTIONS:

- 1. The existing electrical conduits are operational and no new conduits will be required for this system.
- 2. The odor control system includes a bio scrubber, one fan and appurtenances.
- 3. The NPW source is available for the bio scrubber.
- 4. The covers for the headwork channels will be designed as rubber mats.
- 5. No geotechnical work is required. COSL to provide past geotechnical reports for the North WWTP.



| | Description/Task | Carollo Engineers, Inc. | | | | | | | Kuo | | Total Estimated | | |
|-------------|---|-------------------------|--------------------|-----------|---------------------------|-------------------|----------|--------------|--------|---------------------|--------------------|----------|--------|
| Item | | Principal | Project Manager | Engineer | Engineering Technician | Word Processor | Subtotal | Carollo Cost | | Survey Cost (\$) | | Fee (\$) | |
| | | Technologist | | | | | (hrs) | | | | | | |
| | | \$ 230.00 | \$ 210.00 | \$ 133.00 | \$ 120.00 | \$ 90.00 | | | 1.7 | | | | |
| Task 1 | Project Management (2 months) | 7 | 22 | 24 | 0 | 4 | 57 | \$ | 9,782 | \$ | - | \$ | 9,782 |
| 1.1 | Project Scheduling | 0 | 4 | 8 | 0 | 0 | 12 | \$ | 1,904 | | | \$ | 1,904 |
| 1.2 | Project Status Report | 3 | 6 | 0 | 0 | 0 | 9 | \$ | 1,950 | | | \$ | 1,950 |
| 1.3 | Project Work Plan | 2 | 4 | 8 | 0 | 0 | 14 | \$ | 2,364 | | | \$ | 2,364 |
| 1.4 | Project Meetings | | | | | | | | | | | | |
| | Kick-off meeting | 2 | 2 | 2 | 0 | 1 | 7 | \$ | 1,236 | | | \$ | 1,236 |
| | 30% Submittal Meeting | 0 | 2 | 2 | 0 | 1 | 5 | \$ | 776 | | | \$ | 776 |
| | 60% Submittal Meeting | 0 | 2 | 2 | 0 | 1 | 5 | \$ | 776 | | | \$ | 776 |
| | 90% Submittal Meeting | 0 | 2 | 2 | 0 | 1 | 5 | \$ | 776 | | | \$ | 776 |
| Task 2 | Final Design Services | 31 | 38 | 128 | 90 | 70 | 357 | \$ | 49,234 | \$ | - | \$ | 49,234 |
| 2.1 | Prepare Design Documents (Drawings and Specifications) | 14 | 32 | 100 | 90 | 70 | 306 | \$ | 40,340 | | | \$ | 40,340 |
| 2.2 | QA/QC | 16 | 2 | 4 | 0 | 0 | 22 | \$ | 4,632 | | | | |
| 2.3 | Cost Estimate | 1 | 4 | 24 | 0 | 0 | 29 | \$ | 4,262 | | | \$ | 4,262 |
| Task 3 | Bidding Assistance (1 month) | 4 | 12 | 22 | 16 | 12 | 66 | \$ | 9,366 | \$ | - | \$ | 9,366 |
| 3.1 | Issusance of Addenda | 1 | 2 | 6 | 4 | 4 | 17 | \$ | 2,288 | | | \$ | 2,288 |
| 3.2 | Conduct Pre-bid Meeting | 2 | 2 | 0 | 0 | 0 | 4 | \$ | 880 | | | \$ | 880 |
| 3.3 | Respond to Bidder's Questions | 1 | 4 | 8 | 0 | 0 | 13 | \$ | 2,134 | | | \$ | 2,134 |
| 3.4 | Conformed Documents | 0 | 4 | 8 | 12 | 8 | 32 | \$ | 4,064 | | | \$ | 4,064 |
| SUBTOTALS | | 42 | 72 | 174 | 106 | 86 | 480 | \$ | 68,382 | | | \$ | 68,382 |
| | roject Equipment & Communications Expense (PECE) - \$11.70/hr | | | | | | | \$ | 5,616 | | | | |
| | URVEY ALLOWANCE | | | | | | | | | \$ | 3,000 | | |
| | THER DIRECT COSTS (3% OF SUBTOTAL LABOR FEE) | | | | | | | \$ | 2,051 | \$ | - | | |
| SUBCONSULTA | SUBCONSULTANT MARKUP (10% OF SUBCONSULTANT COSTS) | | | | | | | \$ | 300 | | | | |
| | TOTALS | | 72 | 174 | 106 | 86 | 480 | 70 | 6,349 | \$: | 3,000 | \$ | 79,349 |